



SHEET NOTES:

- (1) STEAM TRAP AND DRIP SET ASSEMBLY, TYPICAL. [SEE TYPICAL STEAM METER DETAIL].
- CENTERLINE PIPE ELEVATIONS SHOWN ARE AT VAULT WALL PENETRATIONS.
- 2 1-1/2" SUMP PUMP DISCHARGE LINE, TO STORM DRAINAGE SYSTEM.
- 3 24"ø x 24" LONG REINFORCED CONCRETE SEWER PIPE.
- 4 PIPE SUPPORT IN VAULT, TYPICAL.
- (5) CONCRETE ANCHOR BLOCK, TYPICAL.
- 6 CONDENSATE COOLER. [SEE SANITARY SEWER INSIDE DROP DETAIL].
- 7 24" REINFORCED CONCRETE PIPE AIR VENT.
- (8) CONCRETE GRADE RINGS AS REQUIRED.
- (9) CONCRETE SUPPORT FOR ELBOW, PLACE AGAINST UNDISTURBED EARTH.
- \bigodot [see sanitary sewer manhole detail for termination of manhole access and air vent openings.]
- 1 MANHOLE COVER SHALL BE D&L FOUNDRY MODEL# D-6140 OR EQUAL.
- (2) AIR VENT COVER SHALL BE D&L FOUNDRY MODEL # D-5343 OR EQUAL.

NOTES TO DESIGN PROFESSIONAL:

- 1. VERIFY AND EDIT TEXT IN BRACKETS [].
- VERIFY WITH UNIVERSITY'S REPRESENTATIVE FOR CONDITIONS WHERE DRAINAGE OF SUMP PUMP TO STORM DRAINAGE SYSTEM IS NOT POSSIBLE.

STEAM VAULT TYPICAL LAYOUT

NTS